



**शिवाजी विद्यापीठ , कोल्हापूर  
तंत्रज्ञान अधिविभाग  
निविदा**

शिवाजी विद्यापीठाच्या तंत्रज्ञान अधिविभागातील मुलांच्या वसतिगृहामध्ये CCTV कॅमेरे व वायरींग सहीत इतर यंत्रणा खरेदी करून बसवणेचे आहे. संबंधित साहित्याचे स्पेसिफिकेशन्स सोबत जोडलेले आहेत. संबंधित CCTV कॅमेरे व इतर यंत्रणा पुरविणेसाठी लिफाफा बंद दरपत्रके शिवाजी विद्यापीठाच्या आवक / जावक विभागामार्फत खालील पत्त्यावर दिनांक १८/०८/२०२३ पर्यंत जमा करणेत यावीत. प्रति, संचालक , C/O रेक्टर , मुलांचे वसतिगृह, तंत्रज्ञान अधिविभाग, शिवाजी विद्यापीठ ,विद्यानगर, कोल्हापूर ४१६००४

**दिनांक: ०८/०८/२०२३ डॉ. व्ही. एन. शिंदे ( प्रभारी कुलसचिव )**

Sr. No.	Description of Material	Qty Nos	Amount inclusive GST and other taxes with one year warranty	Total amount in Rs
Section A				
1	<u>HD Bullet IR Camera :</u> High quality imaging with 5MP, 2560 x 1944 resolution, Digital WDR, 3.6 mm fixed focal lens, Smart IR, up to 30 m IR distance, One port for four switchable signals (TVI/AHD/CVI/CVBS)	2		
2	<u>HD Doom IR Camera ;</u> High quality imaging with 5 MP, 2560 x 1944 resolution, Digital WDR, 3.6 mm fixed focal lens, Smart IR, up to 20 m IR distance, One port for four switchable signals (TVI/AHD/CVBS)	32		
3	<u>16 CH HD DVR :</u> Self-adaptive HDTV/HDCVI/AHD/CVBS signal input, Up to 2-ch 6 MP IP cameras input, 5 MP / 4 MP HDTV video input and live view, Connectable to H.265+/H.265/H.264+/H.264 IP cameras, Full channel recording at up to 5 MP resolution, Simultaneous HDMI ( up to 4k (3840 x 2160) resolution )/VGA output, 2 SATA interfaces (up to 8 TB capacity per HDD), 8-ch synchronous playback, Smart search for efficient playback, Supports line crossing detection and intrusion detection of all channels, and 2-ch sudden scene change detection, 1 RJ45 10M/100M/1000M self-adaptive Ethernet , Output bandwidth limit configurable, Metal Body.	3		
4	4 TB Surveillance Hard Disk WD Purple.	5		
5	16 Ch 10 Amp CC Camera Power Supply for CCTV Cameras Branded	2		
6	BNC Connector	64		
7	Power Connector	32		
8	PVC box for Camera fitting	32		
9	Network Rack : 4U Size, with cooling fan and power strip	2		
Section B CCTV Cabling Work Approx Casing Work 50 Meter and cable laying work 90 Meter				
1	Supply and fitting of ¾" ( 20/25MM ) casing with labour charges	Meter		
2	Supply and fitting of 1" (25/32 MM) Casing with labour charges	Meter		
3	Supply and fitting of 2" (50/20 MM) Casing with labour charges	Meter		
4	Labour charges for cable laying in casing	Meter		
	Approx, Grant Total Rs			